

# TEMPORARY CHANGE REQUEST

TCR NO. **TCR-ENG-028,R2-001**

(e.g., TCR-ENG-021,R0-001)

The Temporary Change Request (TCR) Form is to be used to process urgent or minor changes for PPPL Policies, Organization/Mission Statements and Procedures. The TCR should be used when changes are:  
1) urgent, and can not wait the 2-4 week period for Department Head review/comment, or  
2) minor, and do not warrant Department Head review.

Person Requesting Change: Les Hill Phone Ext: 2674

Department Name: Director's Office (IOI)

Document Number: ENG-028 Revision No.: 2

Document Title: Core Boring, Cutting and Drilling

## Reason for change:

ENG-028 is not implementable as written for the volume of penetrations involved with IOI construction and the organizational and safety management framework unique to the IOI project. IOI construction is being carried out by a general contractor (Whiting Turner) and its subcontractors and the work is being performed under a Health and Safety Plan (HASP) and reviewed by the ESH Department Head and approved by the IOI Project Manager.

Title Updates.

**Change description:** (Summarize and attach changed pages, with changes clearly indicated)

- Added: NOTE: For the IOI project, an IOI project-specific penetration procedure will be developed, reviewed, approved and integrated in the Whiting Turner Health and Safety Plan. This procedure will have controls equivalent to those provided in ENG-028 tailored for use on the IOI project. The procedure will be reviewed by the ESH Department Head, PPPL Fire Protection AHJ and approved by the IOI Project Manager.

- Updated Titles and Organizations names, added management system, records and training sections.

1. Does this TCR significantly alter the intent or scope of the document? YES: \_\_\_\_\_ NO: X

2. Does this TCR significantly impact **ES&H**? YES: \_\_\_\_\_ NO: X

If 1 or 2 is **YES**, Explain why the changes should not be routed for Department Head review:

Les Hill 3/30/17  
Department/Division Head Approval Date

James B. Graham 3/30/17  
Head, Best Practices/Quality Assurance/Quality Control Date

Release/Effective date of this TCR: 4/3/17

Incorporate this TCR into next revision of this document? YES: \_\_\_\_\_ NO: X

PPPL	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 1 of 6</b>
<b>Subject:</b>  <b>Core Boring, Cutting and Drilling</b>	<b>Effective Date:</b>  April 28, 2010	<b>Initiated by:</b>  Head, Facilities and Site Services	
	<b>Supersedes:</b> TCR ENG-028, R1-003 Dated: 4/1/2005	<b>Approved:</b>  Director	

TCR-ENG-028,R2-001

**Management System (Primary):** 08 Facilities and Property Management  
**Management System Owner:** Head, Facilities and Site Services  
**Management Process:** 08.17 Fire Protection and Life Safety  
**Process Owner:** Head, Facilities and Site Services  
**Sub-Process:** 08.17.04 Hazards Identification and Control  
**Sub-Process Owner:** Head, Facilities and Site Services  
**Subject Matter Experts (SMEs):** Penetration Engineer

TCR-ENG-028,R2-001

## 1.0 PURPOSE

This procedure establishes the minimum requirements for the drilling, cutting, or core boring of partial or full-through penetrations to any depth in walls, floors, and ceilings at PPPL.

**NOTE: For the IOI project, an IOI project-specific penetration procedure will be developed, reviewed, approved and integrated in the Whiting Turner Health and Safety Plan. This procedure will have controls equivalent to those provided in ENG-028 tailored for use on the IOI project. The procedure will be reviewed by the ESH Department Head, PPPL Fire Protection AHJ and approved by the IOI Project Manager.** TCR-ENG-028,R2-001

## 2.0 SCOPE

2.1 The specific minimum requirements for the boring, drilling or cutting of penetrations in walls, floors and ceilings at PPPL are included in the procedure. The procedure is broken up into two Sections. The first section addresses evolutions where a Core/Drilling Permit is not required and has minimal requirements. The second section addresses drilling/core boring requiring the full requirements of this procedure. Additionally, the following attachments are included:

1. Attachment 1 Core Boring, Cutting and Drilling Generic Requirements, Prerequisites and Precautions
2. Attachment 2 Core Boring and Drilling Permit (typical)
3. Attachment 3 Core Boring and Drilling Field Procedure (typical)
4. Attachment 4 Subcontractor Statement of Work for new D-Site Core Boring Operations (typical)
5. Attachment 5 Qualification of Individuals for the Operation of Sub-surface Scanning Equipment

## SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT

TCR-ENG-028,R2-001

### 3.0 DEFINITIONS

**Cognizant Individual/ATI** – The Cognizant or Accountable Technical Individual responsible for the system or item that passes through the new penetration or that requires a physical modification to an existing penetration. Manages approvals and documentation for the particular job and assures the Seal and/or Coring/Drilling Installers compliance with this procedure.

**Coring/Drilling Installer** -The person(s) performing construction & installation operations are referred to as the “Coring/Drilling Installer” in this procedure. This may be an outside contractor or a PPPL employee.

**Penetration Engineer** – The designated engineer that maintains the database of penetration numbers inspects and approves the start of work on new penetrations and specifies penetration fire seal design.

**Qualified Person** – The designated individual who is qualified to operate the sub-surface scanning equipment per the requirements of Attachment 5 of this procedure.

### 4.0 REFERENCES

1. ESH-004, Job Hazard Analysis
2. ESH-016, Control of Hazardous Energy (Lockout/Tagout)
3. ENG-027, Fire Barrier Penetration Seal Installation and Repair
4. P-012, Stop Work Authority

### 5.0 PROCEDURE

#### 5.1 SITUATIONS NOT REQUIRING A CORE BORING AND DRILLING PERMIT

5.1.1 The Figure below provides guidance/requirements for specific situations where a Core Boring and Drilling Permit is not required.

Material	Depth	Type of Drilling	Requirements
Sheet Rock	$\leq 1 \frac{1}{2}$ “	Drill	Class “0” gloves/ Scanned by qualified person
Poured Concrete/Hollow Concrete Block	$\leq 1 \frac{3}{4}$ “	Drill/Coring	Class “0” gloves/ Scanned by qualified person
Hollow Concrete Block	Any	Chisel/hammer	Class “0” gloves/ Scanned by qualified person
Metal Walls/Ceilings/Floors	Any	Drill/Coring	Class “0” gloves/AC Power concurrence

**Figure 1 Situations not Requiring a Coring/Drilling Permit**

## SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT

TCR-ENG-028,R2-001

Responsibility	Action
<b>Cognizant Individual/ATI</b>	<ol style="list-style-type: none"> <li>Once the determination has been made that a floor, ceiling, or wall will need to be penetrated will determine whether Section 5.1 or 5.2 of this procedure is applicable by referencing Figure 1.</li> <li>If the work needing to be performed falls within the guidance of Figure 1, PROCEED with this Section; otherwise, PROCEED to Section 5.2.</li> <li>If the work to be performed requires that a through-hole be cored, drilled, or chiseled CONTACT the Penetration Engineer so that the requirements of ENG-027 can be employed.</li> <li>Obtains Class "0" voltage rated gloves which are required to be worn while drilling, coring, or chiseling.</li> <li>If drilling into poured concrete, hollow concrete block, or sheet rock, contacts a Qualified Person to have the area scanned for rebar, conduits, or other utilities.</li> </ol>
<b>Qualified Person</b>	<ol style="list-style-type: none"> <li>Performs sub-surface scan (with approved equipment) of affected area to determine if rebar, conduit, or other utilities are present in the affected area.</li> </ol> <p>NOTE: A person is qualified by satisfactorily completing Attachment 5 of this procedure.</p> <p style="text-align: center;"><b>CAUTION:</b></p> <p>If it is thought that any rebar, conduit, or other utility may be in the affected area the assumption shall be made that it is a conduit housing live conductors. Alternate solutions for the location of the drilling will be made.</p>
<b>Cognizant Individual/ATI</b>	<ol style="list-style-type: none"> <li>If it is desired to drill/core in areas that are thought to be rebar only, contacts either the Fabrication and Operations Division Head or the Head, Facilities and Site Services for permission to continue.</li> <li>For drilling into metal ceilings, floors, or walls AC Power shall be consulted to ensure that no electrical issues are present. Follows the advice of AC Power. This step shall be performed in addition to visual checks of the structure being breached.</li> </ol>

TCR-ENG-028,R2-001

**SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT**

TCR-ENG-028,R2-001

9. Using voltage rated gloves performs the drilling, coring, or chiseling operation as required following the advice of AC power.

**5.2 SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT**

1. This section applies to situations not covered by Figure 1.

<b>Responsibility</b>	<b>Action</b>
<b>Cognizant Individual/ATI</b>	1. For all through-holes contacts the Penetration Engineer to discuss the drilling/penetration location and general requirements as required by ENG-027.
<b>Penetration Engineer</b>	2. Ensures the requirements of ENG-027 are employed for a new penetration and coordinates the activities as needed. 3. Informs the ATI to prepare a statement of work (Attachment 4) and requisition if an outside subcontractor will be performing the boring, cutting or drilling. 4. Informs the ATI to issue a written procedure (Attachment 3) incorporating the requirements, prerequisites and precautions of Attachment 1.
<b>Cognizant Individual/ATI</b>	5. Completes the requirements of Attachment 3 as follows: <ol style="list-style-type: none"> <li>a. Marks the desired location(s) and numbers on the floor and wall of the building itself prior to the start of any pre-job surveys. (Note: Numbers will be assigned by the Penetration Engineer).</li> <li>b. Arranges for a sub-surface survey of drilling/coring area with approved scanning equipment to attempt to identify any embedded rebar, conduits or other utilities.</li> <li>c. Contacts AC Power to ensure they perform an AC power check.</li> </ol>
<b>Qualified Person</b>	6. Performs sub-surface scan (with approved equipment) of affected area to determine if rebar, conduit, or other utilities are present in the affected area.  NOTE: A person is qualified by satisfactorily completing Attachment 5 of this procedure.
	7. Signs Attachment 3 if the affected area is clear of rebar and utilities.

## SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT

TCR-ENG-028,R2-001

8. Records any comments in space provided.

**Responsibility****Action****CAUTION:**

If it is thought that any rebar, conduit, or other utility may be in the affected area the assumption shall be made that it is a conduit housing live conductors. Alternate solutions for the location of the drilling will be made.

**Cognizant  
Individual/ATI**

9. If it is desired to drill/core in areas that are thought to be rebar only, contacts either the Fabrication and Operations Division Head or the Head, Facilities and Site Services for permission to continue.

TCR-ENG-028,R2-001

**Fabrication and  
Operations Division  
Head/Head,  
Facilities and Site  
Services**

10. If satisfied that no conduits or other utilities will be breached, signs Attachment 3. TCR-ENG-028,R2-001

**Power Systems  
Branch Head**

11. Once satisfied that no conduits are present in the affected area, signs Attachment 3.

**Penetration  
Engineer**

12. Once all of the requirements of Attachment 3 have been completed, issues a Core Boring and Drilling Permit (Attachment 2) and updates the penetration database.

**Coring/Drilling  
Installer**

13. Satisfies all applicable requirements and prerequisites listed in Attachment 1 prior to commencing work.
14. Performs all work to provide for a complete installation in accordance with applicable requirements and precautions listed in Attachment 1, the approved penetration procedure, and drawings.

**SITUATIONS REQUIRING A CORE BORING AND DRILLING PERMIT**

TCR-ENG-028,R2-001

**Training** TCR-ENG-028,R2-001Head, Facilities and  
Site Services**A. Target Audience:** Penetration Engineer, System Engineers, Facilities Engineers, AC Power group.Instructor: Head, Facilities and Site Services

Training Method:

 Read only Email distribution only

Frequency:

 Once only Other: Upon changes to this procedure**Records Requirements Specific To This Procedure** TCR-ENG-028,R2-001

Records Custodians must assure records are maintained as follows:

Record Title	Record Custodian	Location	Retention Time
Core Boring and Drilling Permit	Penetration Engineer	Penetration Engineer Files	Cut off at the close of the FY. Destroy 75 yrs after discontinuance of facility. <i>Reference Admin 18: Security, Emergency Planning and Safety Records (9)</i>
Subcontractor Statement of Work For New D-Site And C-Site Core Boring Operations	Operations Center	Operations Center	Lifetime of project
Qualification of Individuals for the Operation of Sub-Surface Scanning Equipment	Penetration Engineer	Penetration Engineer Files	Cut off at the time of separation or transfer of the employee. Screen out and destroy all item 29.1.a.(4) records. Transfer folders with remaining documents to the local Federal Records Center. Destroy 4 years after cutoff. - All other performance plans and ratings. <b>Hold indefinitely – DOE</b> <i>Reference Admin 1 Personnel Records (29.1.a)</i>

**Attachments** TCR-ENG-028,R2-001

1. Core Boring, Cutting and Drilling Generic Requirements, Prerequisites & Precautions
2. Core Boring and Drilling Permit
3. Core Boring and Drilling Field Procedure
4. Subcontractor Statement of Work for New D-Site and C-Site Core Boring Operations
5. Qualification of Individuals for the Operation of Sub-Surface Scanning Equipment

<b>PPPL</b>	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 1 of 2</b>
<b>Core Boring, Cutting and Drilling Generic Requirements, Prerequisites &amp; Precautions</b>			<b>Attachment 1</b>

TCR-ENG-028,R2-001

## **CORE BORING, CUTTING AND DRILLING GENERIC REQUIREMENTS, PREREQUISITES and PRECAUTIONS**

### **REQUIREMENTS**

1. Overcuts are not permitted unless noted on the approved drawing.
2. All work shall take place under the supervision of the PPPL Penetration Engineer.
3. Penetrations Permits, and where applicable Flame Permits, shall be obtained prior to starting each penetration.
4. All work requires preparation of a job hazard analysis (JHA) and review of the JHA by all workers at a pre-job briefing prior to starting work (see procedure ESH-004).
5. For work involving boring, cutting or drilling within or into a radiologically controlled area (RCA), PPPL Health Physics must be consulted; and will specify any required radiological precautions (e.g., radiological surveys, water filtering and direction to LEC tanks, personal protective equipment, etc.) in a Radiation Work Permit (RWP) prior to the start of drilling.
6. Installer must install polyethylene sheeting on both sides of the cuts to protect existing equipment.
7. The cutting equipment must be grounded and plugged into a "Ground Fault Interrupter" adapter or circuit, and the mechanic must wear Class "0" electrical insulating gloves provided by ES&H. All persons in the area must not make any other body contact with the cutting machine unless additional insulating measures are taken. An assistant operating a vacuum machine to remove water from the floor, which is potentially in electrical contact with a ground fault (severed conductor), must wear rated gloves as a minimum.
8. Safety goggles and steel toed shoes must be worn by all persons near the drilling/cutting operations.
9. The installer is responsible for securing all cut-out portions / plugs to assure that they do not fall (especially ceiling and floor cut-outs / plugs).
10. Personnel must be available on the breakthrough side of the cut at the time of the breakthrough and equipment must be protected as specified by the cog engineer. If open holes exist in the general area of the cut personnel must monitor the work area and break through side throughout the cutting process or limit the cooling water introduced.
11. The work area must be wiped down and cleaned periodically during the cutting process. Radiation Work Permits (RWPs) may require that; material used for wiping must be released by PPPL Health Physics prior to disposal.
12. The installer must provide temporary seals for the penetrations as soon as they are completed in a manner acceptable to the Penetration Engineer.
13. The installer will install any necessary scaffolding in accordance with the requirements of PPPL ES&H Directive 5008, Section 1, Item 1.6.2.
14. The installer must provide any lift equipment needed to get equipment onto the scaffolding.
15. The installer must provide cutting tools capable of handling the rebar that exists in the location being cut / drilled.



<b>PPPL</b>	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 2 of 2</b>
	<b>Core Boring, Cutting and Drilling Generic Requirements, Prerequisites &amp; Precautions</b>		<b>Attachment 1</b>

TCR-ENG-028,R2-001

## **PREREQUISITES**

Installers shall ensure the following prerequisites are completed prior to commencement of activities:

1. Obtain work permit(s) for any work in the Experimental Areas as required by OP-AD-09. D-Site Work Permits.
2. Obtain approval of a Core Boring and Drilling Permit (Attachment 2) prior to performing any work involving drilling a new penetration.
3. Schedule work on the Rollover Schedule in order to minimize interference with other activities.
4. Schedule any work requiring health physics support with the Health Physics Manager
5. Notify QC and the Facility Manager for the area prior to start of work.

## **PRECAUTIONS**

Installer shall ensure the following precautions are taken prior to and during activities:

1. Become familiar with, and avoid damaging existing facilities, equipment, cable trays, and cables of all voltages. Walking or standing on a cable tray is not permitted without the approval of the Electrical Safety Engineer. (See form 5008.2-1, "Permit for climbing or walking on cable trays"). The Penetration Engineer can be contacted to help get approvals.
2. Contact the Shift Supervisor prior to starting work in the Experimental Areas. It should be noted that testing may be in progress and certain areas are hazardous due to the presence of live equipment/bus work in close proximity to the work area.
3. Wear hard hats in posted areas. Gloves, safety goggles, face shields, respirators, etc. shall be worn as specified by Industrial Hygiene (IH).
4. Ensure that the work is properly planned and safe physical supports are provided; in particular, ladders, platforms, etc. must be used in accordance with ES&HD-5008, Environmental Safety & Health Manual.
5. Observe all safety requirements for work as required by the Shift Supervisor and/or the Construction Manager.
6. Perform all work in accordance with ES&HD-5008, PPPL Environmental Safety & Health Manual. Installer shall ensure that all safety barricades and signs set up by others are obeyed.
7. Wear disposable dust masks, goggles and/or protective equipment, for any work that produces chips or dust from drilling, cutting or grinding or as specified by Industrial Hygiene (IH). Final Clean up shall be with a vacuum and/or mop (wet method) as determined by the installer.
8. Obtain a check by a Health Physics representative of all equipment, material, hardware, and devices to be removed from radiologically controlled areas (RCAs) if so required by the Radiation Work Permit (RWP).
9. Secure the area at the end of each work shift to assure safe conditions.

<b>PPPL</b>	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 1 of 1</b>
	<b>Core Boring and Drilling Permit</b>		<b>Attachment 2</b>

TCR-ENG-028,R2-001

## Core Boring and Drilling Permit

**ATI / Design Engineer:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Penetration Number:** \_\_\_\_\_

**ECN#:** \_\_\_\_\_

**WP#:** \_\_\_\_\_

**Procedure #:** \_\_\_\_\_

**Reference Drawing(s):** \_\_\_\_\_

**Cost Center:** \_\_\_\_\_ **Work Package:** \_\_\_\_\_ **Job:** \_\_\_\_\_

### PENETRATION LOCATION & DESCRIPTION

**Site:** \_\_\_\_\_ **Bldg. / Area:** \_\_\_\_\_ **Floor Elevation:** \_\_\_\_\_ **Fire Rating:** \_\_\_\_\_

**Nearest Bldg. Columns:** \_\_\_\_\_ **Located On: Wall or Ceiling or Floor**

**Type: Circular or Rectangular** \_\_\_\_\_ **Sleeve: Yes or No**

**Center or Bottom Elevation of Penetration:** \_\_\_\_\_ **Gross Area:** \_\_\_\_\_

**System(s)/Service:** \_\_\_\_\_

**Equipment Passing through Pen (Pipe, conduit, etc):** \_\_\_\_\_

**Field Walkdown Performed? Yes or No or N/A** \_\_\_\_\_ **By:** \_\_\_\_\_

**Required Drawings Reviewed? Yes or No or N/A** \_\_\_\_\_ **By:** \_\_\_\_\_

### SCHEDULE & APPROVAL

**Penetration Engineer Approval to Proceed:** \_\_\_\_\_

**Penetration Permit No.:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Work to be Performed Starting (Date):** \_\_\_\_\_

**Duration (Days/Weeks)** \_\_\_\_\_

**Estimated Resealing Date:** \_\_\_\_\_ **Actual Date:** \_\_\_\_\_

**Field Work Performed by:** \_\_\_\_\_

## New Penetration Boring, Cutting and Drilling Procedure

For Penetration(s) \_\_\_\_\_

Prepared by: \_\_\_\_\_  
ATI/Design Engineer

This procedure is for cutting and drilling of penetrations in areas **except** radiologically Controlled Areas (RCAs).

For cutting and drilling in RCAs, see the Penetration Engineer for further instructions.

### 1.0 SCOPE

This document describes the penetration(s) that need to be installed as described in Core Boring and Drilling Permit(s).

<u>Permit No.</u>	<u>ATI / Cognizant Engineer</u>
-------------------	---------------------------------

This document describes how the work must be performed and lists the portions of work that are the responsibility of PPPL and those that are the responsibility of the subcontractor.

### 2.0 PREREQUISITES AND REQUIREMENTS

- 2.1. The mechanics performing the work must take and pass PPPL General Employee Training (GET) if penetration work is expected to last longer than 5 working days.
- 2.2. PPPL will mark the locations of penetrations on the floors and walls using 1 ½" permanent lettering.

Penetration Locations Marked \_\_\_\_\_  
ATI/Cognizant Engineer      Date

- 2.3. **The Coring/Drilling Installer is responsible for securing all cut out portions/plugs** to assure that they do not fall (especially ceiling/floor cut-outs). Personnel must be available on the breakthrough side of the cut at the time of breakthrough.
- 2.4. The contractor will supply and install any necessary scaffolding in accordance with the requirements of PPPL ES&H Directive 5008, Section 1, Item 1.6.2. All scaffolding must be reviewed and approved by the PPPL Competent Person for scaffolding (see <http://www-local.pppl.gov/eshis/OSHACPs.pdf>) prior to their use.
- 2.5. Water associated with the concrete core boring is to be collected and not allowed to spread beyond the work area.
- 2.6. PPPL will review facility drawings and survey the penetration areas with a sub-

TCR-ENG-028,R2-001

surface scanner approved by the Head, Facilities and Site Services or Head, Engineering and Infrastructure to attempt to identify any embedded utilities.

2.6.1	<p>Scan Results and Comments</p> <p>Scan Completed: _____ Date: _____  <small>Qualified Individual</small></p> <p>Comments:</p>
2.6.2	<p>A.C. Power is notified and in agreement.</p> <p>A.C. Power Signoff: _____ Date: _____  <small>Power Systems Branch Head</small></p> <p>Comments:</p>
2.6.3	<p>Permission to core or drill into suspected rebar (Fabrication and Operations Division Head or the Head, Facilities and Site Services)</p> <p style="text-align: right; color: red; font-size: small;">TCR-ENG-028,R2-001</p> <p>Signoff: _____ Date: _____</p>

- 2.7. The cutting equipment must be grounded and plugged into a “Ground Fault Interrupter” adapter or circuit, and the mechanic must wear Class “0” electrical insulating gloves. All persons in the area must not make any other body contact with the cutting machine unless additional insulating measures are taken.
- 2.8. The work area must be wiped down and cleaned periodically during the cutting process and after the work has been completed.
- 2.9. The contractor must provide cutting tools capable of handling the rebar that exists in these locations. See comments from the rebar scan above.
- 2.10. Safety goggles and steel toed shoes must be worn by all persons near the drilling/cutting operations.
- 2.11. PPPL will install any sleeves required in the penetrations.
- 2.12. PPPL will provide temporary seals for the penetrations if needed.
- 2.13. QA should be used to monitor the work in progress.
- 2.14. Penetration permits, and where applicable Flame Permits shall be obtained by PPPL personnel prior to starting each penetration.
- 2.15. If previously undocumented conduit is discovered, a STOP WORK must be immediately enacted and Policy P-012 must be followed.

**SUBCONTRACTOR STATEMENT OF WORK FOR  
NEW D-SITE AND C-SITE CORE BORING OPERATIONS**

This document is applicable for Penetration Number(s)

\_\_\_\_\_  
(List Penetration Numbers)

In Support of

\_\_\_\_\_  
(List System or Components That Pass Through Penetration(s))

Prepared by: \_\_\_\_\_  
ATI/Cognizant Engineer

Reviewed by: \_\_\_\_\_  
ES&H Manager

Reviewed by: \_\_\_\_\_  
Quality Assurance

Approved by: \_\_\_\_\_  
Penetration Engineer

<b>PPPL</b>	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 2 of 3</b>
	<b>SUBCONTRACTOR STATEMENT OF WORK FOR NEW D- SITE AND C-SITE CORE BORING OPERATIONS</b>		<b>Attachment 4</b>

TCR-ENG-028,R2-001

## 1.0 SCOPE

This document describes the penetrations that need to be installed for:

---

System / Penetrating Item

This document also describes how the work must be performed and lists the portions of work that are the responsibility of PPPL and those that are the responsibility of the subcontractor. *(This attachment is a suggested format and content that must be tailored to the specific work it is to be used for.)*

The penetration sizes and locations are:

<i><b>Penetration Number</b></i>	<i><b>Description</b></i>
----------------------------------	---------------------------

*(list all applicable penetrations, and a short description of size and location of the penetration)*

## 2.0 APPLICABLE DOCUMENTS

- 2.1 PPPL Environmental, Safety and Health Manual, PPPL ESH 5008 (requires compliance with OSHA regulations).
- 2.2 List of Applicable PPPL Drawings

<i><b>Penetration Number</b></i>	<i><b>Drawing Name and Number</b></i>
----------------------------------	---------------------------------------

<b>PPPL</b>	<b>PRINCETON PLASMA PHYSICS LABORATORY</b>	<b>PROCEDURE</b>	<b>No. ENG-028, Rev. 2 page 3 of 3</b>
	<b>SUBCONTRACTOR STATEMENT OF WORK FOR NEW D- SITE AND C-SITE CORE BORING OPERATIONS</b>		<b>Attachment 4</b>

TCR-ENG-028,R2-001

### 3.0 PREREQUISITES AND REQUIREMENTS

The requirements and precautions listed below are condensed from Attachment 1. All parties involved with this particular job are responsible for reading the full list of precautions and conditions.

#### 3.1 PPPL Responsibilities

1. PPPL will mark the locations of the penetrations on the floor and walls.
2. PPPL will install polyethylene sheeting or other measures on both sides of the cuts to protect existing equipment.
3. PPPL will provide access to 208v or 480v welding receptacles as required.
4. Water associated with the concrete core boring is to be filtered and sent directly to a liquid effluent collection system drain, or as otherwise directed by PPPL Health Physics. The plug removed from the core drilling shall be turned over to HP.
5. PPPL will review facility drawings and survey the penetration areas with a rebar meter to attempt to identify any embedded conduits. If a conduit is thought to be in the cutting area, the contractor must limit the supply of cooling water. Attempts will be made to de-energize any conduits found prior to starting drilling.
6. PPPL personnel must be available on the breakthrough side of the cut at the time of the breakthrough and equipment must be protected as specified by the cog engineer.
7. PPPL will install any sleeves required in the penetrations.
8. PPPL will provide temporary seals for the penetrations if needed.
9. QA should be used to monitor the work in progress.
10. Penetrations Permits, and where applicable Flame Permits, shall be obtained by PPPL personnel prior to starting each penetration.

#### 3.2 Contractor Responsibilities

1. The mechanics performing the work must take and pass PPPL General Employee Training (GET) if penetration work is expected to last longer than 5 working days.
2. The contractor will supply and install any necessary scaffolding in accordance with the requirements of PPPL ES&H Directive 5008, Section 1, Item 1.6.2. All scaffolding must be reviewed and approved by the PPPL Construction Manager prior to their use.
3. The cutting equipment must be grounded and plugged into a "Ground Fault Interrupter" adapter or circuit, and the mechanic must wear Class "0" electrical insulating gloves. All persons in the area must not make any other body contact with the cutting machine unless additional insulating measures are taken.
4. The work area must be wiped down and cleaned periodically during the cutting process and after the work has been completed.
5. The contractor must provide cutting tools capable of handling the 1" rebar that exists in these locations.
6. Safety goggles and steel toed shoes must be worn by all persons near the drilling/cutting operations.
7. The contractor is responsible for securing all cut-out portions / plugs to assure that they do not fall.

**PPPL**

**PRINCETON PLASMA  
PHYSICS LABORATORY**

**PROCEDURE**

**No. ENG-028, Rev. 4  
page 1 of 1**

**Qualification of Individuals for the Operation of  
Sub-Surface Scanning Equipment**

**Attachment 5**

TCR-ENG-028,R2-001

**Name:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Sub-surface scanning equipment being qualified on:** \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

**Document the training completed:** \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Submitted by:** \_\_\_\_\_  
Penetration Engineer

**Date:** \_\_\_\_\_

**Reviewed by:** \_\_\_\_\_  
Fabrication, Operation and Maintenance Division Head

**Date:** \_\_\_\_\_

**Approved by:** \_\_\_\_\_  
Head, Facilities and Site Services

**Date:** \_\_\_\_\_